EZ SIGNS, LLC

1839 Bustleton Pike

Feasterville, PA 19053

P: 1 (866) 349-5444

F: (215) 676-3269

EZ SIGNS **LLC** 1 (866) FIX-LIGHT

November 25, 2024

Re: Sign Install for Courtyard by Marriott

1419-27 ARCH ST

Scope of work:

SIGN A - Replace one (1) statically LED-lit accessory channel letter sign on raceway mounted and connected to existing power, 42.56 SF.

SIGN B1; B1; B2 - Replace three (3) NON-lit wall plaque panels w/ new NON-lit painted black S/F 8" \times 1'-6" \times 1" deep w/ waterjet cut aluminum letters painted white, 1.1 SF each.

SIGN C - Replace two (2) NON-lit canopy routed panels painted black w/ push-thru copy. Like-to-like, change of copy only. Sizes and location will remain the same; 11 SF each.

SIGN D - Replace one (1) NON-lit routed canopy panel painted black w/ push-thru copy. Like-to-like, change of copy only. Sizes and location will remain the same; 7.9 SF

SIGN E - Replace one (1) statically LED-lit accessory channel letters on existing Raceway and connect power supplies to existing power; 101.74 SF

SIGN F - Replace one (1) NON-lit wall panel sign 6 SF

SIGN G - Replace one (1) NON-lit wall panel sign 6 SF

Natalya Atroshyna

EZ SIGNS LLC

1839 Bustleton Pike

Feasterville, PA 19053

p. 267-406 - 0273

e. permits@signsinstall.com



COURTYARD BY MARRIOTT


1421 Arch St AKA 1419-27 ARCH ST PHILADELPHIA, PA 19102





L.E.D. CHANNEL LETTER MOUNTING DETAIL (EXTERIOR)

- A. .050" x 3" PAINTED TO MATCH PMS 426 C GRAY, SATIN FINISH
- B. 1" JEWELITE PAINTED TO MATCH PMS 426 C GRAY, SATIN FINISH
- C. .050" ALUMINUM BACKS
- D. 3/16" #2447 WHITE POLYCARBONATE FACES
- E. WHITE GE TETRA MAX 7100K LEDS F. POWER CABLE LOW VOLTAGE SHIELDED W/ STRAIN RELIEF STARTING FROM POWER SUPPLY THEN LETTER TO LETTER (BEHIND FASCIA)
- THEN LETTER TO LETTER (BEHIND FASC G. 1/4" WEEP HOLES AS REQUIRED (FOR EXTERIOR INSTALLATION ONLY)
- H. SILICONE BEAD AROUND THE INSIDE OF RETURN AND BACK TO SEAL FROM WATER LEAKAGE
- I. L BRACKET ATTACHED TO RACEWAY FOR MOUNTING
- J. 1/2* SEALTITE CONDUIT RUNNING TO SECONDARY CONNECTION * NOTE: GENERAL CONTRACTOR TO HAVE PRIMARY CONNECTION HOOKED UP
- K. STANDARD POWER SUPPLY HOUSE IN A 3" X 3" EXISTING RACEWAY & BY MARRIOTT W/ NEW RACEWAY & TUBING FOR MOUNTING (TBV)





Scope of work:

Replace one (1) statically LED-lit accessory channel letter sign on raceway mounted and connected to existing power.


18" COURTYARD CHANNEL LETTERS ATTACHED TO EXISTING RACEWAY 8 11/16" BY MARRIOTT CHANNEL LETTERS ATTACHED TO NEW RACEWAY UNDER GLASS CANOPY RACEWAY TO HAVE L BRACKET FOR MOUNTING w/ TUBING (TBV)

18" WHITE CHANNEL LETTERS RW MOUNT • 42.56 SQ FT / QTY: 1

1/4" = 1'-0"









Scope of work:


Replace three (3) NON-lit wall plaque panels w/ new NON-lit painted black S/F 8" x 1'-6" x 1" deep w/ waterjet cut aluminum letters painted white.

8" X 1'-6" X 1" DEEP PANEL ROUTED & BACKED W/ FCO LETTERS / QTY: 1 OF EACH

1" = 1'-0"









Scope of work:

1'-2" X 9'-6" ROUTED PANELS w/ PUSH-THRU COPY / QTY: 2

Replace two (2) NON-lit canopy routed panels painted black w/ push-thru copy. Like-to-like, change of copy only. Sizes and location will remain the same.

BUILDING SIGNAGE







7.9 SQ FT

Scope of work:

Replace one (1) NON-lit routed canopy panel painted black w/ push-thru copy. Like-to-like, change of copy only. Sizes and location will remain the same

1'-2" X 6'-10" ROUTED PANELS w/ PUSH-THRU COPY / QTY: 1

3/4" = 1'-0"


BUILDING SIGNAGE






L.E.D. CHANNEL LETTER MOUNTING DETAIL (EXTERIOR)

- A. .050" x 3" PAINTED TO MATCH PMS 426 C GRAY, SATIN FINISH
- B. 1" JEWELITE PAINTED TO MATCH PMS 426 C GRAY, SATIN FINISH
- C. .050° ALUMINUM BACKS
- D. 3/16" #2447 WHITE POLYCARBONATE FACES W/ PERFORATED VINYL TO MATCH PMS 426 C GRAY, SATIN FINISH
- F. 1/2* SEALTITE CONDUIT RUNNING TO SECONDARY CONNECTION * NOTE: GENERAL CONTRACTOR TO HAVE PRIMARY CONNECTION HOOKED UP
- G. 3/8" THREADED RODS WITH 2" x 4" WOOD BLOCKING AS REQUIRED TO MOUNT RACEWAY TO WALL





Scope of work:

Replace one (1) statically LED-lit accessory channel letters on existing Raceway and connect power supplies to existing power.



30" WIREWAY MOUNT CHANNEL LETTERS GRAY DAY/WHITE NIGHT • 101.74 SQ FT / QTY: 1

3/16" = 1'-0"

BUILDING SIGNAGE














2' x 3' x 1" DEEP ALUMINUM WALL PANEL PAINTED BLACK W/ FCO LETTERS/ QTY: 1 OF EACH

Scope of work:


1. Remove existing wall NON-lit plaques and replace w/ new panel painted black / S/F 2' x 3' x 1" Deep w/ Waterjet cut aluminum letters painted white.


1/2" = 1'-0"

PROPOSED SIGNS:

- A 18" WHITE CHANNEL LETTERS RW MOUNT 42.56 SQ FT
- B1 8" X 1'-6" X 1" DEEP PANEL ROUTED & BACKED W/ FCO LETTERS / QTY: 2 OF EACH
- 8" X 1'-6" X 1" DEEP PANEL ROUTED & BACKED W/ FCO LETTERS / QTY: 1 OF EACH
- 1'-2" X 9'-6" ROUTED PANELS w/ PUSH-THRU COPY QTY:2

- 1'-2" X 6'-10" ROUTED PANELS w/ PUSH-THRU COPY
- 30" WIREWAY MOUNT CHANNEL LETTERS 101.74 SQ FT
- 2' x 3' x 1" DEEP ALUMINUM WALL PANEL PAINTED BLACK W/ FCO LETTERS/ QTY: 1 OF EACH
- G 2' x 3' x 1" DEEP ALUMINUM WALL PANEL PAINTED BLACK W/ FCO LETTERS/ QTY: 1 OF EACH







Philadelphia, Pennsylvania 19106 phone: 215.829.0922 facsimile: 215.829.0596

Associate Architect: 1617 Walnut Street Philadelphia, Pennsylvania 19103 phone: 215.564.1007 facsimile: 215.564.3311

Development Services Group 866 Ridgeway Loop Memphis, TN 38120 phone: 901.747.3946

The Hotel at 1421 Arch Street Philadelphia, PA

Site Plan

Warning: Actual Conditions may vary from conditions shown on this drawing, confirm all information in the field before proceeding with any work and notify the Architect in writing if a variation is discovered.

This drawing is an instrument of professional services and shall not be modified, copied or used for another project without the written consent of the Architect.

Date	Comments	
5/30/2007	PROGRESS SET	
6/1/2007	HISTORICAL PROGRESS SET	
6/5/2007	PROGRESS SET	
6/13/2007	HISTORICAL SET	
7/13/2007	PROGRESS SET	
8/07/2007	PRICING SET	
10/16/07	PRICING REVISION	<u> </u>
11/21/07	CONSTRUCTION SET	
1/7/08	FINAL CONSTRUCTION	SET
8/14/09	RECORD SET	

06.118 AS NOTED Checked By:

BHA Job Number:

Approved By: